OFFICE OF THE SUPERINTENDENT, POWER AND LIGHT, MYSORE.

*Abstract Notification dated 9th August 1938.*

Attention of the public is invited to the detailed Notification appearing on pages 1422 to 1423 of Part VI of the *Mysore Gazette*, dated 18th August 1938 in connection with the installation of electric lights and heating circuit to the Out Patient Dispensary attached to the New Chéluvamba Maternity Hospital, Mysore.

---

*Notification dated 12th August 1938.*

1. Sealed tenders in triplicate will be received at the Office of the Superintendent, Power and Lighting, Mysore, superscribed with the name of the work mentioned below.

2. The plans connected with the wrok may be seen at the Office of the undersigned at all working hours. The copy, if required, will be made available on payment of Rs. 2 per set.

3. The tenders should be drawn up strictly in conformity with the specifications furnished, writing out the rates at which each item of work will be executed, in figures as well as in words failing which no cognizance will be taken of the tender. No items other than those noted in the statement should be included as the items cover provision for all sundries, repairs to damaged masonry and painting.

4. The materials to be used on the work should be of best quality conforming to the specification of this Department and B. S. or A. I. E. E. specification. Mention should also be made of the manufacture and the catalogue numbers of the materials offered. Teak wood planks to be used on the work should be free from cracks, knots and well seasoned. No planks less than 12" in width will be permitted to be used unless it is to make up the difference in size of the board required. Only the lap joints should be adopted in all cases.

5. The undersigned reserves the right to reject the tenders without assigning any reason therefor.

6. The successful tenderer will be required to deposit an earnest money of Rs. 50 (Rupees fifty only) and execute an agreement within a week from the date of intimation of acceptance of the tender. He should send samples of all the materials required for the work mounted on a board and start the work after obtaining the approval of the undersigned with regard to the same and carry out the wiring following the rules of this Department as well as that of the Institution of Electrical Engineers. He should also be prepared to adopt any change in the location of control points and other outlets that might be suggested by the undersigned during the progress of the work without extra cost if the tender is not materially affected by such deviations.

7. The undersigned reserves the right also to reject the work either in full or in part if he finds the work not carried out in terms of the specifications or is otherwise dissatisfied with the workmanship.

8. *Name of work.*—Installing electric lights and ceiling fan, etc., to the extension of the Office of the Loco & Carriage Superintendent, Mysore State Railway, Mysore.

9. *Last date for receiving tenders.*—29th August 1938, 3 P.M.

10. *Date and time of opening the tenders in public.*—29th August 1938, 4 P.M.

11. A period of four weeks will be allowed for final completion of the work with effect from the date of final acceptance of the tender. A penalty of rupees ten for each day's delay over and above the stipulated period during the first week and rupees twenty during the second week will be imposed. If there be further delay, the Department will take charge of the installation at whatever stage it might be and arrange for its completion through any other agency entirely at the risk of the tenderer.

12. The wiring contractors should bind themselves to attend to any major troubles that might crop up in the installation due to bad workmanship, etc., within 12 calendar months from the date of handing over the installation to this Department without any obligation.

13. *Details of work.*—The quantities given in the following statement are not guaranteed and are subject to variation at the time of executing the work.

| | | |
|---|---|---|
| 1. | Supplying and laying No. 7/.044 SWG twin conductor paper insulated lead covered, double steel tape armoured, jute served, underground cable, suitable for 1,000 volts pressure in a trench 3 feet deep surrounding the same with 3" of fine sand enclosing the ends in indoor and pole type junction boxes (cast iron) filled with insulating compound and the exposed portion of the cable at the pole end in 18 ft. of 2" galvanised pipe with bends, clamps, etc., using No. 7/.044 SWG 660 volts grade insulated wire and accessories ... | 75 Rft. |
| 2. | Supplying and running mains in ¾" W. I. pipe using No. 7/.044 SWG 660 volts grade insulated wire and accessories ... | 5 R.ft. |
| 3. | Earthing ... | Item |
| 4. | Supplying, fixing and wiring T. W. board 27"×21"×1" with battens and rear board equipping it with a D. P. S. T. iron clad switch with fuses 30 amps. one 10 amp. per way 6 way D. P. D. O. pattein distribution box in metal case, with 10 amp. circuit switches with reinforced bakelite cover, using No. 7/.044 and 7/.029 SWG 660 volts grade insulated wire and accessories ... | One. |
| 5. | Supplying and running circuit mains in T. W. 2-way 2"×1" casing treated with 2 coats of shellac varnish using No. 7/.029 SWG 660 volts grade insulated wire and accessories (for connecting up the existing circuit) ... | 150 ft. |

| | | |
|---|---|---|
| 6. | Supplying, fixing and wiring in T. W. 2-way 2″×1″ casing treated with 2 coats of shellac varnish for drop lights complete with 2 plate bakelite ceiling rose, twin flexible cord reinforced bakelite crod grip B. C. lamp holder 5 amp. control switch with reinforced bakelite cover using No. 7/.029 and 3/.029 SWG 250 volt grade insulated wire (for mains and taps respectively) and accessories. | Nine. |
| 7. | Do do do for ½″ braized conduit pendants 2 to 3 ft. long complete with stout ceiling plate B. C. C. G. lamp holder, 5 amp. control switches as per specification above | 4 |
| 8. | Do do do for B. C. Back-plate type lamp holder, bakelite as per specification above | 3 |
| 9. | Do do do for O. C. brackets 6″×½″ with O. C. B. C. lamp holder, 5 amp. control switches, etc., as per specification above | 2 |
| 10. | Supplying, fixing and wiring for ceiling fan 220/230 volts, A. C. 60 cycles, 56″ sweep 3 curved alluminium blades, complete with shackle, canopy standard length of down rod, 5 point variable speed choke type regulator, suitable with hollow spindle, finished in white with gold lines, using suitable suspension clamp, etc., as per specification in previous items | Two |
| 11. | Do do do attached with a lighting fixture underneath it, using B. C. lamp holder, green and white 10″×5½″ opal shade, 5 amp. control switches, etc., as per above specification | One. |
| | Do do do using the available ceiling fan and lighting unit, as per specification above | One. |
| 13. | Suplpying and fixing globes 6″×3¼″ opal | 3 |
| 14. | Supplying and fixing shades white opal 10″ | 11 |
| 15. | Do do tin enamelled | 4 |
| 16. | Do do lamps 40/60 watts, 220 volts, gas filled pearl or internally frosted | 19 |

*N.B.*—All the released materials from the old installation should be handed over to this Department.

*Notification dated 22nd August* 1938.

Sealed tenders in triplicate will be received at the Office of the Superintendent, Power and Lighting, Mysore, superscribed with the name of the work mentioned below.

2. The plans connected with the work may be seen at the office of the undersigned at all working hours.

3. The tenders should be drawn up strictly in accordance with the specifications furnished at the same time *writing out the rates at which each item of work is executed in figures as well as in words* failing which no cognizance is taken of the tender. No items other than those noted in the statement should be included in the tender as the items include provision for all sundries, repairs to damaged masonry and painting the casings, boards, etc.

4. The materials to be used on the work should be of best manufacture, conforming to the departmental wiring rules and the latest B.S. or A.I.E.E. specifications and *mention should clearly be made of the manufacture and catalogue numbers of the materials offered.* The T.W. planks, etc., to be used on the work should be well seasoned and free from knots and white wood and cracks. The minimum width of the plank to be used to boards, etc., should be not less than 12 inches unless it is to make up the difference in size of the board required. In all cases lap joints should be adopted. In no case joints would be permitted to be put up diagonally for the boards.

5. The undersigned reserves the right to reject the tenders without assigning any reason therefor.

6. The successful tenderer will be required to deposit on earnest money of Rs. 80 (rupees eighty) in cash and execute an agreement within a week from the date of intimation as to the acceptance of the tender, failing which the tender will be disposed of otherwise at his risk.

7. In executing the work, the wiring rules of the Department as well as those of the Institution of Electrical Engineers should be strictly followed.

8. The successful tenderer should be prepared to carry out any change in the location of the fixtures that might be suggested by the undersigned during the course of the work, without any extra cost, if the estimate is not materially affected by such deviations. The undersigned reserves the right to reject the work in full or in part if he finds the work not executed in terms of the specification.

9. The successful tenderer should send a board fitted up with samples of all the materials offered in connection with the work to the undersigned and start the work only after obtaining approval for use of the same on the work.

10. It will be obligatory on the part of the tenderer to attend to any troubles that might develop due to bad workmanship in the installation within the period of first twelve months from the date of handing over the installation to this Department free of any charges.

11. *Name of work* :—Installing electric lights and wall plugs to the Block 'H' at the Exhibition buildings, Mysore.

12. The last date and time for receiving the tenders is 29th August 1938 at 3 P.M.

13. The time and date for opening the tenders in public is 29th August 1938 at 4 P.M.

14. A period of two weeks is the time within which the work is expected to be completed in all respects from the date of acceptance of the tender, failing which a penalty of Rs. 25 (rupees twenty five) for each day of delay over and above the stipulated period will be enforced.

15. *Details of work* :—The quantities given in the statement attached are not guaranteed and are subject to change during the execution of the work.

| | *Names of materials, etc.* | *Quantity.* |
|---|---|---|
| 1. | Supplying and running 3 phase, 25 cycle mains in 2" W.I. Pipe with bends clamps, etc., using No. 19/·083 SWG insulated wire and accessories | 30 ft. |
| 2. | Do single phase mains, using No. 7/·044 SWG. insulated wire and accessories (pipe, clamps and bends available) | 30 " |
| 3. | Supplying, fixing and wiring T.W. board 3'×2'×1" with 2" batten and ½" rear board equipping it with— (*a*) One T.P.S.T. iron clad switch 30 amps. with fuses for the general lighting, (*b*) One D.P.S.T. iron clad switch 30 amps. for the yard lighting. (*c*) One do do for 60 cycle feeder, (*d*) Two D.P.S.T. iron clad switches 50 amps. with fuses for the additional lighting circuits using No. 19/·083, 7/·064 and 7/·036 SWG. insulated wires and accessories | One. |
| | *N.B.*—One D.P.S.T. and one T.P.S.T. iron clad switches are available. | |
| 4. | Supplying and running circuit mains 3 phase in 2"×1" T.W. casing treated with 2 coats of shellac varnish using No. 7/·036 SWG. insulated wire and accessories | 500 ft. |
| 5. | Supplying, fixing and wiring in 2"×1" 2 way teak wood casing treated with 2 coats of shellac varnish for braized conduit pendants 3'×½" complete with stout ceiling plate, B.C. lamp holder, etc., using No. 3/·029 SWG insulated wire and accessories (to be equally distributed on all the 3 phases) | 41 |
| 6. | Supplying and running single phase 25 cycle mains in 2"×1" teak wood 2—way casing treated with 2 coats of shellac varnish using No. 7/·064 SWG insulated wire and accessories | 480 ft. |
| 7. | Supplying and running single phase 60 cycle mains in 2"×1" teak wood casing 2 way treated with 2 coats of shellac varnish using No. 7/·036 SWG insulated wire and accessories | 480 " |
| 8. | Supplying, fixing and wiring in 2"×1" teak wood casing 2 way treated with 2 coats of shellac varnish for bakelite 5 amp. plug sockets with hand shield plugs on 60 cycle circuit using No. 3/·029 SWG insulated wire and accessories | 41 |
| 9. | Do do for 2 pin non-interlocking all insulated switch plugs with slot type switch 5 amp. on 25 cycle supply using No. 3/·036 SWG insulated wire and accessories | 41 |
| 10. | Supplying and running mains in ¾" W.I. Pipe embedded in the wall using No. 7/·044 SWG insulated wire and accessories | 8 ft. |
| 11. | Connecting up the compound lighting cable with the mains using suitable indoor type cast iron junction boxes and accessories | Item. |
| 12. | Earthing the main pipe and metal clad switches, etc. | Item. |

M. HAYATH,
*Superintendent.*

## MYSORE STATE RAILWAY.

OFFICE OF THE CONTROLLER OF STORES, MYSORE SOUTH, MYSORE.

*Notice dated 17th August* 1938.

Dealwood boxes, crates, planks, wooden barrels and gunny bags, etc., will be sold by public auction by the undersigned at the Railway Central Stores, near the Railway Central Workshops, Mysore South, on Sunday the 11th September 1938 at 8-30 A.M.

The lots will be available for inspection near the premises on 9th and 10th September 1938 between 8 and 11 A.M.

Full amount of the purchase made should be paid immediately a lot is knocked down. Lots should be taken charge by the purchaser before evening. Lots not removed within two days from the date of auction will be considered as unclaimed and sent to the Lost Property Office at the risk of the purchaser.

A Railway material certificate to book on the Mysore State Railway, at Railway material rate will be given to large purchasers of dealwood boxes, etc.

The auction will be conducted in accordance with rules contained in Government Order No. R. S. 2599-605—Ry. 346-G-22-23 of 4th May 1923.

A. SADASIVAN,
*Controller of Stores.*